

AD-A156 415

NATIONAL PROGRAM FOR INSPECTION OF NON-FEDERAL DAMS
BAKER FLOODWATER RESE. (U) CORPS OF ENGINEERS WALTHAM
MA NEW ENGLAND DIV JUL 79


1/2

UNCLASSIFIED

F/G 13/13

NL

[illegible]



NATIONAL BUREAU OF STANDARDS
MICROCOPY RESOLUTION TEST CHART

AD-A156 415

MERRIMACK RIVER BASIN
WENTWORTH, NEW HAMPSHIRE


**BAKER FLOODWATER RESERVOIR
SITE 6**

NH 00243

NHWRB NO. 24901

**PHASE I INSPECTION REPORT
NATIONAL DAM INSPECTION PROGRAM**

Copy available to DTIC does not
warrant fully legible reproduction



**DEPARTMENT OF THE ARMY
NEW ENGLAND DIVISION, CORPS OF ENGINEERS
WALTHAM, MASS. 02154**

STATEMENT A
Approved for public release;
Distribution Unlimited

**JULY 1979
85 06 14 014**

DTIC FILE COPY

UNCLASSIFIED

SECURITY CLASSIFICATION OF THIS PAGE (When Data Entered)

REPORT DOCUMENTATION PAGE		READ INSTRUCTIONS BEFORE COMPLETING FORM
1. REPORT NUMBER NH 00243	2. GOVT ACCESSION NO.	3. RECIPIENT'S CATALOG NUMBER
4. TITLE (and Subtitle) Baker Floodwater Reservoir Site 6 NATIONAL PROGRAM FOR INSPECTION OF NON-FEDERAL DAMS		5. TYPE OF REPORT & PERIOD COVERED INSPECTION REPORT
7. AUTHOR(s) U.S. ARMY CORPS OF ENGINEERS NEW ENGLAND DIVISION		6. PERFORMING ORG. REPORT NUMBER
9. PERFORMING ORGANIZATION NAME AND ADDRESS		8. CONTRACT OR GRANT NUMBER(s)
11. CONTROLLING OFFICE NAME AND ADDRESS DEPT. OF THE ARMY, CORPS OF ENGINEERS NEW ENGLAND DIVISION, NEDED 424 TRAPELO ROAD, WALTHAM, MA. 02254		10. PROGRAM ELEMENT, PROJECT, TASK AREA & WORK UNIT NUMBERS
14. MONITORING AGENCY NAME & ADDRESS (if different from Controlling Office)		12. REPORT DATE July 1979
		13. NUMBER OF PAGES 88
		15. SECURITY CLASS. (of this report) UNCLASSIFIED
		16a. DECLASSIFICATION/DOWNGRADING SCHEDULE
16. DISTRIBUTION STATEMENT (of this Report) APPROVAL FOR PUBLIC RELEASE: DISTRIBUTION UNLIMITED		
17. DISTRIBUTION STATEMENT (of the abstract entered in Block 20, if different from Report)		
18. SUPPLEMENTARY NOTES Cover program reads: Phase I Inspection Report, National Dam Inspection Program; however, the official title of the program is: National Program for Inspection of Non-Federal Dams; use cover date for date of report.		
19. KEY WORDS (Continue on reverse side if necessary and identify by block number) DAMS, INSPECTION, DAM SAFETY, Merrimack River Basin Wentworth New Hampshire Pond Brook		
20. ABSTRACT (Continue on reverse side if necessary and identify by block number) The dam is an earthen structure consisting of homogeneous silty sand and earth fill on a bedrock foundation. The inspection revealed that the dam is in good condition. It is intermediate in size with a significant hazard classification. There are various remedial measures which should be implemented by the owner.		

DISCLAIMER NOTICE

**THIS DOCUMENT IS BEST QUALITY
PRACTICABLE. THE COPY FURNISHED
TO DTIC CONTAINED A SIGNIFICANT
NUMBER OF PAGES WHICH DO NOT
REPRODUCE LEGIBLY.**



DEPARTMENT OF THE ARMY
NEW ENGLAND DIVISION, CORPS OF ENGINEERS
424 TRAPELO ROAD
WALTHAM, MASSACHUSETTS 02154

REPLY TO
ATTENTION OF:
NEDED

FEB 14 1960

Honorable Hugh J. Gallen
Governor of the State of New Hampshire
State House
Concord, New Hampshire 03301

Dear Governor Gallen:

Inclosed is a copy of the Baker Floodwater Reservoir Site 6 Phase I Inspection Report, which was prepared under the National Program for Inspection of Non-Federal Dams. This report is presented for your use and is based upon a visual inspection, a review of the past performance and a brief hydrological study of the dam. A brief assessment is included at the beginning of the report. I have approved the report and support the findings and recommendations described in Section 7 and ask that you keep me informed of the actions taken to implement them. This follow-up action is a vitally important part of this program.

A copy of this report has been forwarded to the Water Resources Board, the cooperating agency for the State of New Hampshire and the owner of the dam.

Copies of this report will be made available to the public, upon request, by this office under the Freedom of Information Act. In the case of this report the release date will be thirty days from the date of this letter.

I wish to take this opportunity to thank you and the Water Resources Board for your cooperation in carrying out this program.

Sincerely,

MAX B. SCHEIDER
Colonel, Corps of Engineers
Division Engineer

Incl
As stated

BAKER FLOODWATER RESERVOIR SITE 6

NH 00243

NHWRB 249.01

MERRIMACK RIVER BASIN
WENTWORTH, NEW HAMPSHIRE

Accession For	
NTIS GRA&I	<input checked="" type="checkbox"/>
DTIC TAB	<input type="checkbox"/>
Unannounced	<input type="checkbox"/>
Justification	
By	
Distribution/	
Availability Codes	
Dist	Avail and/or Special
A/1	23 WY

PHASE I INSPECTION REPORT
NATIONAL DAM INSPECTION PROGRAM



NATIONAL DAM INSPECTION PROGRAM
PHASE I - INSPECTION REPORT
BRIEF ASSESSMENT

Identification No.: 00243
Name of Dam: Baker Floodwater Reservoir Site 6
Town: Wentworth
County and State: Grafton, New Hampshire
Stream: Pond Brook
Date of Inspection: May 16, 1979


Baker Floodwater Reservoir Site 6 dam is an earthen structure consisting of homogeneous silty sand and earth fill on a bedrock foundation. Overall length of the dam is 203 feet. The height from the top of embankment to the streambed is 13 feet. Maximum structural height is 17 feet. Top width of the dam is 12 feet and the slope of the upstream and downstream embankments is 3 horizontal to 1 vertical. A concrete spillway discharges through the center of the dam. The spillway has two crests, a high stage and a low stage. In addition, there is a 3.0 foot by 3.1 foot slop log gate which is used as a pond drain. The dam construction was completed in June of 1973. Plans, design calculations and construction data were prepared by the Soil Conservation Service and are available for inspection.

The visual inspection revealed that the dam is in good condition. The visual inspection revealed surface drainage from the right abutment, surface cracks and deterioration of the concrete walls of the spillway, and deficient rip-rap at the contact point of the inlet structure and the embankment.

Based on the intermediate size of the dam and its significant hazard classification and in accordance with Corps of Engineers Guidelines, the test flood inflow should be of a magnitude ranging from $\frac{1}{4}$ the Probable Maximum Flood (PMF) to the full PMF. A test flood inflow equal to $\frac{1}{4}$ the PMF or 12,700 cfs, was used. The routed test flood outflow of 8600 cfs overtops the dam by 3.2 feet. With the water surface at the top of dam the spillways will have a capacity of 4200 cfs (or 49 percent of the routed test flood outflow). The hydraulic design calculations indicate that the low level spillway crest was designed for up to a 100 year frequency flood. The hydraulic crest of the dam was designed using a total watershed runoff of 4.14 inches.

It is recommended that the owner engage a qualified, registered professional engineer to design a surface water diversion system to eliminate ponding of water on the right side of the spillway wall and to evaluate the condition of the backfill adjacent to the wall. Remedial measures include the development of a downstream warning system in the event of emergency conditions and replenishing of deficient rip-rap at the contact of the inlet structure and the embankment.

The recommendations and remedial measures are described in Section 7 and should be addressed within two (2) years, unless otherwise noted, after receipt of this report by the owner.





Gordon H. Slaney, Jr.


Gordon H. Slaney, Jr., P.E.
Project Engineer

Howard, Needles, Tammen & Bergendoff
Boston, Massachusetts

This Phase I Inspection Report on Baker Floodwater Reservoir Site 6 has been reviewed by the undersigned Review Board members. In our opinion, the reported findings, conclusions, and recommendations are consistent with the Recommended Guidelines for Safety Inspection of Dams, and with good engineering judgement and practice, and is hereby submitted for approval.


JOSEPH W. FINEGAN, JR., MEMBER
Water Control Branch
Engineering Division


CARNEY M. TERZIAN, MEMBER
Design Branch
Engineering Division


JOSEPH A. MCELROY, CHAIRMAN
Chief, NED Materials Testing Lab.
Foundations & Materials Branch
Engineering Division

APPROVAL RECOMMENDED:


JOE B. FRYAR
Chief, Engineering Division

PREFACE

This report is prepared under guidance contained in the Recommended Guidelines for Safety Inspection of Dams, for Phase I Investigations. Copies of these guidelines may be obtained from the Office of Chief of Engineers, Washington, D.C. 20314. The purpose of a Phase I Investigation is to identify expeditiously those dams which may pose hazards to human life or property. The assessment of the general condition of the dam is based upon available data and visual inspections. Detailed investigation and analyses involving topographic mapping, subsurface investigations, testing and detailed computational evaluations are beyond the scope of a Phase I Investigation; however, the investigation is intended to identify any need for such studies.

In reviewing this report, it should be realized that the reported condition of the dam is based on observations of field conditions at the time of inspection along with data available to the inspection team. In cases where the reservoir was lowered or drained prior to inspection, such action, while improving the stability and safety of the dam, removes the normal load on the structure and may obscure certain conditions which might otherwise be detectable if inspected under the normal operating environment of the structure.

It is important to note that the condition of a dam depends on numerous and constantly changing internal and external conditions, and is evolutionary in nature. It would be incorrect to assume that the present condition of the dam will continue to represent the condition of the dam at some point in the future. Only through continued care and inspection can there be any chance that unsafe conditions be detected.

Phase I inspections are not intended to provide detailed hydrologic and hydraulic analyses. In accordance with the established Guidelines, the Spillway Test Flood is based on the estimated "Probable Maximum Flood" for the region (greatest reasonably possible storm runoff), or fractions thereof. Because of the magnitude and rarity of such a storm event, a finding that a spillway will not pass the test flood should not be interpreted as necessarily posing a highly inadequate condition. The test flood provides a measure of relative spillway capacity and serves as an aide in determining the need for more detailed hydrologic and hydraulic studies, considering the size of the dam, its general condition and the downstream damage potential.

TABLE OF CONTENTS

<u>Section</u>	<u>Page</u>
Letter of Transmittal	
Brief Assessment	
Review Board Page	
Preface	i
Table of Contents	ii-iv
Overview Photo	v
Location Map	vi

REPORT

1. PROJECT INFORMATION	1-1
1.1 General	1-1
a. Authority	1-1
b. Purpose of Inspection	1-1
1.2 Description of Project	1-1
a. Location	1-1
b. Description of Dam and Appurtenances	1-2
c. Size Classification	1-2
d. Hazard Classification	1-2
e. Ownership	1-2
f. Operator	1-2
g. Purpose of Dam	1-2
h. Design and Construction History	1-3
i. Normal Operational Procedure	1-3
1.3 Pertinent Data	1-3
2. ENGINEERING DATA	2-1
2.1 Design Data	2-1
2.2 Construction Data	2-1
2.3 Operation Data	2-1
2.4 Evaluation of Data	2-1

<u>Section</u>	<u>Page</u>
3. VISUAL INSPECTION	3-1
3.1 Findings	3-1
a. General	3-1
b. Dam	3-1
c. Appurtenant Structures	3-2
d. Reservoir Area	3-3
e. Downstream Channel	3-3
3.2 Evaluation	3-3
4. OPERATIONAL PROCEDURES	4-1
4.1 Procedures	4-1
4.2 Maintenance of Dam	4-1
4.3 Maintenance of Operating Facilities	4-1
4.4 Description of any Warning System in Effect	4-1
4.5 Evaluation	4-1
5. HYDRAULIC/HYDROLOGY	5-1
5.1 Evaluation of Features	5-1
a. General	5-1
b. Design Data	5-1
c. Experience Data	5-1
d. Visual Observation	5-1
e. Overtopping Potential	5-1
f. Dam Failure Analysis	5-2
6. STRUCTURAL STABILITY	6-1
a. Visual Observation	6-1
b. Design and Construction Data	6-1
c. Operating Records	6-1
d. Post-Construction Changes	6-1
e. Seismic Stability	6-1

<u>Section</u>	<u>Page</u>
7. ASSESSMENT, RECOMMENDATIONS AND REMEDIAL MEASURES	7-1
7.1 Dam Assessment	7-1
a. Condition	7-1
b. Adequacy of Information	7-1
c. Urgency	7-1
d. Need for Additional Investigation	7-1
7.2 Recommendations	7-1
7.3 Remedial Measures	7-2
7.4 Alternatives	7-2


APPENDIXES

APPENDIX A - INSPECTION CHECKLIST
APPENDIX B - ENGINEERING DATA
APPENDIX C - PHOTOGRAPHS
APPENDIX D - HYDROLOGIC AND HYDRAULIC COMPUTATIONS
APPENDIX E - INFORMATION AS CONTAINED IN THE NATIONAL INVENTORY OF DAMS



Parker River Dam - Site 6 - Overview looking upstream.

REPRODUCED AT GOVERNMENT EXPENSE



NATIONAL DAM INSPECTION PROGRAM
PHASE I INSPECTION REPORT
BAKER FLOODWATER RESERVOIR SITE 6

SECTION 1
PROJECT INFORMATION

1.1 General

a. Authority. Public Law 92-367, August 8, 1972, authorized the Secretary of the Army, through the Corps of Engineers, to initiate a National Program of Dam Inspection throughout the United States. The New England Division of the Corps of Engineers has been assigned the responsibility of supervising the inspection of dams within the New England Region. Howard, Needles, Tammen & Bergendoff has been retained by the New England Division to inspect and report on selected dams in the State of New Hampshire Authorization and notice to proceed were issued to Howard, Needles, Tammen & Bergendoff under a letter of March 30, 1979 from John P. Chandler, Colonel, Corps of Engineers. Contract No. DACW33-79-C-0060 has been assigned by the Corps of Engineers for this work.

b. Purpose

(1) To perform technical inspection and evaluation of non-Federal dams to identify conditions which threaten the public safety and thus permit correction in a timely manner by non-Federal interests.

(2) To encourage and prepare the states to initiate quickly effective dam safety programs for non-Federal dams.

(3) To update, verify and complete the National Inventory of Dams.

1.2 Description of Project

Baker Floodwater Reservoir Site 6, Baker Dam Site 6, is located on Pond Brook approximately 3 miles upstream of Route 25-118 in the Town of Wentworth, New Hampshire. The location of the dam is shown on U.S.G.S. Quadrangle Wentworth, New Hampshire with approximate coordinates N43°53'15" W71°57'30", Grafton County, New Hampshire. The location of the dam is shown on the preceding page.

b. Description of Dam and Appurtenances. Baker Dam Site 6 is an earthen structure consisting of homogeneous silty sand and earth fill on a bedrock foundation. A blanket drainage system is located under the downstream portion of the earth fill. Upstream and downstream faces of the embankment are on a 3 horizontal to 1 vertical slope. Top width of the dam is 12 feet. According to the existing plans the overall length is 203 feet, and the height from the top of embankment to the stream bed is 13 feet.

Appurtenant structures consist of a concrete box inlet drop spillway with high and low stage crests, a pond drain with a 3 foot by 3.1 foot stop log gate control. All inlets discharge through the concrete spillway located in the center of the dam.

Figures 1 and 2, located in Appendix B, show a plan of the dam and appurtenant structures. Photographs of each structure are shown in Appendix C.

c. Size Classification. Intermediate (hydraulic height-13 feet, storage-2240 acre-feet) classification based on storage being between 1000 and 50,000 acre-feet as given in Recommended Guidelines for Safety Inspection of Dams.

d. Hazard Classification. The hazard posed by this dam is classified as significant. Failure of the dam with the pool at the top of dam would result in an average flood wave height of about 12 feet through a reach extending from the dam to a point three miles downstream. One dwelling located about 7 feet above the channel would be affected and a portion of Route 25A would be flooded.

e. Ownership. This dam is owned by the New Hampshire Water Resources Board, 37 Pleasant Street, Concord, New Hampshire.

f. Operator. This dam is maintained and operated by the New Hampshire Water Resources Board. Chairman of the Water Resources Board is Mr. George McGee, Sr.; Mr. Vernon Knowlton is Chief Engineer, Telephone No. 603/271-1110.

g. Purpose of Dam. This dam is used for floodwater control. The normal pool is maintained by the low stage spillway crest. The storage between the low stage spillway crest and the high stage spillway crest is used for flood-water control.

h. Design and Construction History. The construction of this dam was completed in June of 1973. Design and construction inspection of this dam were done by the Soil Conservation Service, Durham, New Hampshire. The construction contractor was Robie Construction Company, Inc.

i. Normal Operating Procedures. The normal pool elevation is maintained at the crest of the low stage spillway crest. Under flood conditions the storage between the low and high stage spillway crests is used to retard flood flows of up to a 100 year frequency flood. The high stage crest is utilized only for floods of greater than a 100 year frequency. The dam does not require any manual operation in order to function.

1.3 Pertinent Data

a. Drainage Area. The area tributary to Baker Dam Site 6 consists of 16.96 square miles of wooded mountainous terrain. There is some development in the watershed consisting mostly of summer camps. Approximately 60 percent of the watershed is tributary to Upper Baker Pond which is located upstream of Lower Baker Pond. Maximum elevation is at 2911 feet MSL, and the crest of the dam is at elevation 906.

The area around the reservoir is mostly wooded. There are some cottages located on the pond known as Lower Baker Pond. The reservoir between the dam and a roadway, located about 3000 feet upstream, is very narrow. The roadway bridge has an opening about 25 feet wide. The larger portion of the reservoir is located upstream of the roadway.

b. Discharge at Dam Site

(1) The outlet works for Baker Dam Site 6 consist of a stop log pond drain, and a box inlet type drop spillway with low and high stage inlets. The invert of the 3 foot by 3.1 foot stop log gate is 890.92 feet MSL. Maximum discharge of the opening when the water level is at the crest of the low stage spillway crest of 894.0 is approximately 54 cfs. The low stage spillway crest is at elevation 894.0 (normal pool). The crest length is 36 feet. Flow is controlled at the weir or by a 18 foot by 1 foot high orifice, which discharges to the main spillway. Capacity of the low stage spillway is 293 cfs when the water surface is at the high stage spillway crest of 900.0. The high stage spillway (emergency spillway) crest is set at elevation 900.0, with the water level at the top of dam (elevation 906.0) maximum capacity of the emergency spillway is 4200 cfs. Note that the maximum discharge of all inlets combined is 4200 cfs as they discharge through the same structure.

(2) There are no records available of maximum discharge at the site.

(3) The total spillway capacity with the water surface at the top of the dam is approximately 4200 cfs at elevation 906.0.

(4) Total spillway capacity with the water surface elevation at the test flood elevation of 908.8 is approximately 5500 cfs.

(5) The total project discharge at the test flood elevation of 908.8 is 8000 cfs.

c. Elevation (feet above MSL)

(1) Streambed at centerline of dam - 890.0

(2) Maximum tailwater - unknown

(3) Invert pond drain - 890.92

(4) Normal pool - 894.0

(5) Full flood control pool - 900.0

(6) Spillway crest (low stage) - 894.0
(high stage) - 900.0

(7) Design surcharge - 902.7

(8) Top dam - 906.0

(9) Test Flood Surcharge - 908.8

d. Reservoir (miles)

(1) Length of Maximum Pool - 1.80

(2) Length of Normal Pool - 1.25

(3) Length of Flood Control Pool - 1.65

e. Storage (gross acre-feet)

(1) Normal Pool - 210

(2) Surcharge Flood Control Pool - 1460

(3) High Stage Spillway Crest Pool - 921

(4) Top of Dam - 2240

f. Reservoir Surface (acres)

- (1) Normal Pool - 121
- (2) Surge Flood Control Pool - 215
- (3) High Stage Spillway Crest - 183
- (4) Test Flood Pool - 230
- (5) Top Dam - 230

g. Dam

- (1) Type - earth
- (2) Length - 203 feet
- (3) Height - 13 feet hydraulic
17 feet structural
- (4) Top Width - 12 feet
- (5) Side Slopes - upstream and downstream 3 horizontal
to 1 vertical
- (6) Zoning - 2 fill zones
- (7) Impervious core - none
- (8) Cutoff - zone 1 fill
- (9) Grout Curtain - none
- (10) Other - none

h. Diversion and Regulating Tunnel

See Section j

i. Principal Spillway

- (1) Type - concrete box inlet drop spillway
- (2) Length of Weir - Low Stage-36 feet
High Stage -154 feet
- (3) Crest Elevation - Low Stage-894.0
High Stage-900.0
- (4) Gates - Stop log gate in low stage spillway crest
3.0 feet by 3.1 feet invert 890.92

(5) U/S Channel - Approach channel for stop log gate 4
foot bottom width

(6) Downstream Channel - The spillway section through the dam is 26 feet wide and about 115 feet long with longitudinal sills at the end. The channel downstream of the dam has a rock bottom with ledge outcroppings. The channel is fairly clear with only minor log debris. Some small trees overhang the channel.

j. Regulating Outlets. The normal pool is maintained by the low stage spillway crest at 894.0. There is a trash rack across the entire spillway section. The stop log pond drain gate (3.0 feet by 3.1 feet) is set into the low stage spillway at invert 890.92. The stop logs are normally in place to the crest of the spillway. There is a 4 foot bottom width approach channel to the stop log gate with an invert of 890.0 at the face of the dam.

SECTION 2 ENGINEERING DATA

2.1 Design

A complete set of design data including layout, hydraulic design, foundation and embankment design, geology and soils reports, structural design, quantities and specifications are available for Baker Dam Site 6. In addition, there are construction drawings available. Design of the dam was done by the Soil Conservation Service, Durham, New Hampshire.

2.2 Construction

The dam construction was completed in June of 1973. A complete record of construction documents were made available. These documents include; as-built plans, job diaries, surveying records, test drilling logs, compaction test results, concrete tests and certificate of completion. Construction was by Rodgers Construction Co., Inc., Brattleboro, Vermont, and was inspected by the Soil Conservation Services, Durham, New Hampshire.

2.3 Operation

Normally the pond drain line gate is closed. The normal level of 894.0 is maintained by the low stage spillway crest. The low stage spillway and reservoir storage is designed to retard runoff from up to a 100 year frequency storm without discharge occurring over the high stage spillway (crest 900.0).

2.4 Evaluation

a. Availability. Engineering data available for Baker Dam Site 6 consists of the information outlined in Sections 2.1 and 2.2. The plans, design data, and construction records are available at the offices of the Soil Conservation Service, Federal Building, Durham, New Hampshire, 03824.

b. Adequacy. A complete set of design and construction data did allow for a definitive review within the confines of this Phase I - Inspection Report. Therefore, the adequacy of this dam is based on the design and construction data reviewed, visual inspection, past performance history and sound engineering judgement.

c. Validity. The field inspection indicated that the external features of Baker Dam Site 6 substantially agree with those shown on the available plans.

SECTION 3
VISUAL INSPECTION

3.1 Findings

a. General. The field inspection of Baker Dam Site 6 was made on May 16, 1979. The inspection team consisted of personnel from Howard, Needles, Tammen & Bergendoff and Geotechnical Engineers, Inc. A representative of the New Hampshire Water Resources Board was also present during the inspection. Inspection checklists, completed during the inspection, are included in Appendix A. At the time of inspection the water level was approximately 0.5 feet above the crest of the low stage spillway. The upstream face of the dam could only be inspected above this water level.

b. Dam. Visual inspection of the dam indicated the dam was in good condition.

The dam consists of a homogeneous earth embankment about 203 feet long with a maximum height of about 13 feet. A box-inlet drop spillway passing through the center of the dam discharges both the low stage spillway and the high stage spillway flows.

The embankment, constructed of silty sand, is founded on bedrock which in some areas is severely weathered. Upstream and downstream foundation drainage blankets were constructed to control possible foundation seepage through weathered or jointed rock.

Visual inspection indicated the dam is in good condition with the exception of the need to control surface drainage from the right abutment, which flows along the upstream toe of the dam. The surface water is ponding along the right training wall of the box-inlet structure. The ponding water is shown in Photo No. 18.

The high water table along the right training wall plus possible frost action due to the fines deposited in the back-fill along the wall may have caused the deterioration of the upstream right training wall. Photos No. 9 & 11 show the right training wall and Photo No. 10 shows the upstream left training wall for comparison.

Crest

The crest of the dam is 12 feet wide and grass covered as shown in Photo No. 5. No misalignment of the crest was observed.

Downstream Slope

The downstream slope is 3 horizontal to 1 vertical and has a good grass cover. No signs of seepage or wet areas were observed, however, at the time of inspection, the pool elevation was approximately at the elevation of the downstream toe. In view of the possible foundation seepage beneath the dam, an inspection of the downstream toe area should be made when the pool is at a higher elevation.

Upstream Slope

The upstream slope is 3 horizontal to 1 vertical and has a good grass cover which at the time of inspection required mowing. Riprap placed at the contact between the inlet structure and the embankment is deficient in some areas as shown in Photo No. 17.

A small surface drainage brook exits from the right abutment and flows along the upstream toe to the box-inlet training wall. Photos No. 19 & 20 show this drainage brook along the toe of the embankment and Photo No. 18 shows the water ponding along the right training wall. This surface drainage has deposited soil fines along the training walls.

c. Appurtenant Structure. The visual inspection of the concrete box spillway with high and low stage inlets, pond drain with a stop log control and the discharge sluiceway channel did not reveal any evidence of stability problems. The concrete surface and vertical alignment of the spillway structure are in good condition except for numerous vertical cracks, staining and deposit of efflorescence around concrete cracks as shown in Photos No. 9 & 10.

The spillway structure, shown in Photos No. 7, 8 & 12, consists of two elements, an overflow control (the low and high stage crests of the spillway) and an open sluiceway type discharge channel. The spillway structure is located in the center of the dam. Visual inspection revealed that the spillway structure appeared to be in good condition except the sluiceway walls which have experienced temperature cracks. Inspection of training walls shows concrete temperature cracks, water staining and evidence of efflorescence, a whitish crystalline deposit at the concrete cracks. A lack of construction joints in the training walls was noted.

The galvanized trash rack at the low stage spillway crest consists of structural steel shapes. The trash rack assembly is in good condition, no rust or peeling of the protective coating was noted, see Photos No. 13 and 14. Debris was noted on the trash rack.

The pond drain structure is located in the center of the spillway and is controlled by stop logs. The pond drain and control stop logs were under water at the time of inspection.

The foundation drainage system has 12-inch diameter outlet pipes on each side of the outlet channel just below the concrete training walls, see Photos No. 15 & 16. A slight outflow was observed from the right side drain pipe, and no flow was observed from the left side drain pipe.

d. Reservoir Area. The area around the reservoir is mostly wooded. There are some cottages on the pond known as Lower Baker Pond. The reservoir between the dam and a roadway bridge located at about 3000 feet upstream of the dam is very narrow. The roadway bridge has an waterway opening of about 25 feet as shown in Photo No. 21. The larger portion of the reservoir is located upstream of the bridge.

e. Downstream Channel. The channel downstream of the dam has a rock bottom with ledge outcroppings. The channel is fairly clear with only minor log debris. Some small trees overhang the channel as seen in Photo No. 22.

3.2 Evaluation

The visual inspection indicates that the dam is in good condition. The visual inspection revealed the following:

- (a) Surface drainage from the right abutment, which causes ponding of water along the upstream spillway walls.
- (b) Temperature cracks and deterioration of the concrete walls of the spillway.
- (c) Rip-rap placed at the contact between the inlet structure and the embankment is deficient in some areas.
- (d) Debris on the trash racks.
- (e) The water level was 11.5 feet below the crest of the dam.

SECTION 4 OPERATIONAL PROCEDURES

4.1 Procedure

Baker Dam Site 6 is used for floodwater control. Under normal operating procedures the dam is left to function as designed. The normal pool level is maintained by the low stage spillway crest in the riser. Flood events up to a 100 year frequency are retarded by reservoir storage between the normal pool elevation and the crest of the high stage spillway. The high stage spillway is utilized only for flood events of greater than 100 year frequency.

4.2 Maintenance of Dam

The dam is inspected on an annual basis by the New Hampshire Water Resources Board and the Soil Conservation Service. Maintenance is undertaken as a result of the inspection on an as needed basis. The dam is visited on a monthly basis by personnel of the New Hampshire Water Resources Board.

4.3 Maintenance of Operating Facilities

Maintenance of the outlet works is performed as in Section 4.2.

4.4 Description of Warning Systems

There are no warning systems in effect for this facility.

4.5 Evaluation

The current operation and maintenance procedure for this facility appear to be adequate to insure that any problems encountered can be remedied within a reasonable period of time. However, the owner should establish a warning system to follow in the event of emergency conditions.

SECTION 5
HYDROLOGY AND HYDRAULIC ANALYSIS

5.1 Evaluation of Features

a. General. Baker Dam Site 6 is an earthen embankment dam 203 feet long with a hydraulic height of 13 feet. The dam is constructed with two fill zones and an earth fill core which extends to bedrock. Appurtenant works consist of a two stage box inlet spillway and a stop log gate that can be used to drain the reservoir.

The dam is used for floodwater control. The dam is classified as intermediate in size having a height of 13 feet and maximum storage of 2,240 acre-feet.

b. Design Data. According to the Soil Conservation Service design data this dam is constructed to retard flood flows of up to a 100 year frequency storm without utilizing the emergency spillway. The design flood control elevation is 900.0 feet or equal to the high stage spillway crest. Total runoff for this condition is 2.88 inches during a six hour Type IIB storm. The design freeboard of the dam was determined using an average watershed runoff of 4.14 inches to give an elevation of 902.7. The inflow hydrograph for Baker Site 6 was developed by combining the hydrograph of flow directly tributary to Lower Baker Pond with the routed hydrograph of flow tributary to Upper Baker Pond. The dam crest elevation of 906.0 was set to provide frost protection. The structure was classified as having a class "B" hazard which is defined as "being located in predominantly rural or agricultural area where failure may cause damage to isolated homes, main highways or major railroads, or cause interruption or use or service of relatively important public utilities.

c. Experience Data. There are no records available of maximum discharge at the dam site.

d. Visual Observations. No evidence of damage to any portion of the project from overtopping was visible at the time of inspection.

e. Test Flood Analysis. Detailed design data is available for this dam, and the basic conditions are noted above in Paragraph b. The hydrologic evaluation was performed using information gathered by field investigation, watershed characteristics and Probable Maximum Flood (PMF) guide curves

prepared by the Corps of Engineers. In accordance with Corps of Engineers guidelines, the significant hazard classification and intermediate size of the dam warrant a test flood magnitude ranging from $\frac{1}{2}$ the Probable Maximum Flood (PMF) to the full PMF. A test flood equal to $\frac{1}{2}$ PMF was used as the available storage of 2,240 acre-feet is on the low end of the size classification range of 1,000 acre-feet to 50,000 acre-feet.

The test flood inflow of 11,700 cfs is based on design computations by the Soil Conservation Service (SCS), which include routing of a portion of the inflow through Upper Baker Pond. The SCS calculations yield an inflow to Lower Baker Pond of 5,120 cfs with an average watershed runoff of 4.15 inches. The test flood runoff of 9.5 inches was proportioned to the SCS inflow to obtain the test flood inflow.

The routed test flood outflow was determined in accordance with Corps of Engineers guidance for Estimating Effect of Surcharge Storage on Maximum Probable Discharge and the hydraulic characteristics of the dam. The stage discharge curve is based on SCS calculations and have been extended for elevations higher than those originally done by the SCS. It should be noted that flow control points in the spillway change from orifice to the high stage crest to the spillway throat width. This can be seen on Page 4 of Appendix "D", and in the SCS calculations at the end of Appendix "D".

The routed test flood outflow was determined to be approximately 8,000 cfs. As the maximum capacity of the spillway is 4,200 cfs (approximately 53 percent of the routed test flood outflow) the dam will be overtopped by 2.8 feet.

f. Dam Failure Analysis. The impact of failure of the dam was assessed using the "Rule of Thumb" Guidance for Estimating Downstream Dam Failure Hydrographs prepared by the Corps of Engineers. The breach discharge was estimated with the water surface at the crest of the dam and a breach width equal to 40 percent of the total length of the dam. The downstream hydrograph is a sum of the breach discharge and the maximum spillway capacity. Prior to the breach of dam the river stage about 1 mile downstream would be about 9.6 feet the spillway at a full capacity of 4,200 cfs. Breach of dam would result in an additional 4,890 cfs for a total of about 9,000 cfs. The reach used for the downstream hydrograph routing is smaller in cross section than the channel immediately downstream of the dam. Thus the flood

stages at the dam and for about 1,000 feet downstream of the dam will be lower than those noted in this report.

The river stage after breach of dam would be about 12.6 feet. This stage would not be reduced appreciably as there is little channel storage. In the reach of 15,000 feet only one dwelling located 7 feet above the channel and 3 miles downstream of the dam would be affected. A portion of Route 25A located 2,000 feet downstream of the dam would be flooded by about 6 feet for a distance of 300 feet along the roadway.

SECTION 6
STRUCTURAL STABILITY

6.1 Evaluation of Structural Stability

a. Visual Observation. The visual inspection Baker Dam Site 6 did not disclose any immediate stability problems. The cracks in the spillway training wall do not present any immediate danger to the dam. The cracks may be due to temperature changes and a lack of construction joints. The ponding along the right training wall may aggravate the situation due to hydrostatic pressure and frost heaving. The surface water should be diverted away from the training wall.

b. Design and Construction Data. Design drawings exist and indicate the dam is a homogeneous embankment of silty sand founded on bedrock. Construction drawings indicate the foundation was to be cleaned to sound rock.

The upstream and downstream slopes are 3 horizontal to 1 vertical.

Upstream and downstream drainage blankets were constructed to intercept seepage that might pass through areas of weathered rock.

The primary and emergency spillway consist of a concrete box-inlet which passes through the center of the embankment.

A review of the construction data available indicates that the dam and appurtenant structures were constructed according to the plans and specifications.

c. Operating Records. No operational records were made available.

d. Post Construction Changes. No post construction changes are apparent.

e. Seismic Stability. The dam is located in Seismic Zone 2 and in accordance with the recommended Phase I guidelines does not warrant seismic analysis.

SECTION 7
ASSESSMENT, RECOMMENDATIONS AND REMEDIAL MEASURES

7.1 Dam Assessment

a. Condition. The visual inspection of Baker Flood-water Reservoir Site 6 indicated the dam is in good condition. The inspection revealed the following:

(1) Surface drainage from the right abutment, which causes ponding of water along the right upstream wall of the spillway.

(2) Temperature cracks and deterioration of the concrete walls of the spillway.

(3) Deficient riprap at the contact between the embankment and the inlet structure.

(4) The low level of the reservoir prevented any meaningful evaluation of seepage.

The hydraulic analysis reveals that the spillways cannot pass the routed test flood without overtopping the dam.

b. Adequacy of Information. A complete set of design and construction data did allow for a definitive review with the confines of this Phase I - Inspection Report. Therefore, the adequacy of this dam is based on the design and construction data review, visual inspection, past performance history and sound engineering judgement.

c. Urgency. This dam is in generally good condition. The recommendations and remedial measures described in Sections 7.2 and 7.3 should, unless otherwise noted, be accomplished within two years of the receipt of this Phase I - Inspection Report by the owner. The recommendation in Section 7.1.a should be accomplished within one year. The remedial measure in Section 7.3.a should be done as part of the regular maintenance.

d. Necessity of Additional Investigation. No additional investigation is needed to complete the Phase I Inspection.

7.2 Recommendations

(a) The owner should engage a qualified registered engineer to design a surface water diversion system that would eliminate ponding of water and erosion along the upstream right training wall of the box-inlet structure. The engineer should also evaluate the condition of the backfill adjacent to the wall to determine if it has become frost susceptible due to deposition of fines from the surface water ponding.

7.3 Remedial Measures

(a) The presently missing riprap adjacent to the inlet structure should be replaced.

(b) Devise a warning system to follow in the event of emergency conditions.

(c) The periodic inspection should be continued on not less than a biennial frequency. Special attention should be given for possible seepage in the area of the downstream toe of the dam, particularly if the reservoir level is high.

(d) Remove debris from trash racks on a regular basis.

(e) Repair all spalled concrete on the spillway and training walls.

7.4 Alternatives

There are no practical alternatives to the recommendations and remedial measures described in Sections 7.2 and 7.3.

APPENDIX A
INSPECTION CHECKLIST

VISUAL INSPECTION CHECK LIST
PARTY ORGANIZATION

PROJECT SITE 6, BAKER DAMDATE May 16, 1979TIME 10:00 AMWEATHER FairW.S. ELEV. 894.5 U.S. - DN.SPARTY:

- | | |
|----------------------------|-----------|
| 1. <u>G. Slaney - HNTB</u> | 6. _____ |
| 2. <u>S. Mazur - HNTB</u> | 7. _____ |
| 3. <u>D. LaGatta - GEI</u> | 8. _____ |
| 4. <u>C. Osgood - GEI</u> | 9. _____ |
| 5. _____ | 10. _____ |

PROJECT FEATURE	INSPECTED BY	REMARKS
1. <u>Dam</u>	<u>D. LaGatta, C. Osgood</u>	
2. <u>Spillway, Outlet Works</u>	<u>S. Mazur</u>	
3. <u>and Downstream Channel</u>	<u>G. Slaney</u>	
4. _____		
5. _____		
6. _____		
7. _____		
8. _____		
9. _____		
10. _____		

PERIODIC INSPECTION CHECK LIST

A-2

PROJECT BAKER SITE NO. 6 DAM DATE May 16, 1979
PROJECT FEATURE Earth Embankment NAME D. P. LaGatta
DISCIPLINE Geotechnical Engineer NAME C. E. Osgood

AREA EVALUATED	CONDITION
<u>DAM EMBANKMENT</u>	
Crest Elevation	906.0
Current Pool Elevation	894.5
Maximum Impoundment to Date	unknown
Surface Cracks	None observed
Pavement Condition	No pavement
Movement or Settlement of Crest	None observed
Lateral Movement	None observed
Vertical Alignment	No misalignment observed
Horizontal Alignment	No misalignment observed
Condition at Abutment and at Concrete Structures	Good except for collection of surface water at the right training wall and loss of riprap against wall.
Indications of Movement of Structural Items on Slopes	None
Trespassing on Slopes	No evidence of trespassing was observed.
Sloughing or Erosion of Slopes or Abutments	None except for slight erosion of the upstream face of the embankment adjacent to the right training wall.
Rock Slope Protection - Riprap Failures	No failure. Some riprap missing adjacent to walls of box-inlet spillway.
Unusual Movement or Cracking at or near Toes	None
Unusual Embankment or Downstream Seepage	None observed
Piping or Boils	None observed
Foundation Drainage Features	Two blanket drains, exits are clear.
Toe Drains	None observed
Instrumentation System	None
Vegetation	Grass cover generally good

PERIODIC INSPECTION CHECK LIST

A-3

PROJECT SITE 6, BAKER DAM

DATE May 16, 1979

PROJECT FEATURE Intake Channel/Structure

NAME D. LaGatta, C. Osgood

DISCIPLINE Geotechnical/Structural Engs.

NAME S. Mazur

AREA EVALUATED	CONDITION
<u>OUTLET WORKS - INTAKE CHANNEL AND INTAKE STRUCTURE</u>	
a. Approach Channel	None
Slope Conditions	
Bottom Conditions	
Rock Slides or Falls	
Log Boom	None
Debris	Some at trash rack
Condition of Concrete Lining	
Drains or Weep Holes	
b. Intake Structure	
Condition of Concrete	Good
Stop Logs and Slots	Galvanized trash rack and concrete surface of intake structure are in good condition. Control stop logs at bottom release structure were under water.

PERIODIC INSPECTION CHECK LIST

A-4

PROJECT SITE 6, BAKER DAM

DATE May 16, 1979

PROJECT FEATURE _____

NAME _____

DISCIPLINE _____

NAME _____

AREA EVALUATED

CONDITION

OUTLET WORKS - CONTROL TOWER

a. Concrete and Structural

General Condition

Condition of Joints

Spalling

Visible Reinforcing

Rusting or Staining of Concrete

Any Seepage or Efflorescence

Joint Alignment

Unusual Seepage or Leaks in Gate Chamber

Cracks

Rusting or Corrosion of Steel

b. Mechanical and Electrical

Air Vents

Float Wells

Crane Hoist

Elevator

Hydraulic System

Service Gates

Emergency Gates

Lightning Protection System

Emergency Power System

Wiring and Lighting System

This facility has no control tower.

PERIODIC INSPECTION CHECK LIST

PROJECT SITE 6, BAKER DAM

DATE May 16, 1979

PROJECT FEATURE _____

NAME _____

DISCIPLINE _____

NAME _____

AREA EVALUATED

CONDITION

OUTLET WORKS - TRANSITION AND CONDUIT

General Condition of Concrete

None

Rust or Staining on Concrete

Spalling

Erosion or Cavitation

Cracking

Alignment of Monoliths

Alignment of Joints

Numbering of Monoliths

PERIODIC INSPECTION CHECK LIST

PROJECT SITE 6, BAKER DAM DATE May 16, 1979
 PROJECT FEATURE Outlet Structure/Channel NAME D. LaGatta, C. Osgood
 DISCIPLINE Structural/Hydraulic/Geotechnical NAME S. Mazur, G. Slaney

AREA EVALUATED	CONDITION
<u>OUTLET WORKS - OUTLET STRUCTURE AND OUTLET CHANNEL</u> General Condition of Concrete Rust or Staining Spalling Erosion or Cavitation Visible Reinforcing Any Seepage or Efflorescence Condition at Joints Drain Holes Channel Loose Rock or Trees Overhanging Channel Condition of Discharge Channel	Good Water staining, spillway training walls. None None observed None Efflorescence at surface cracks. Good Open and draining at both walls of box inlet Channel open, free of obstruction None Clear

PERIODIC INSPECTION CHECK LIST

A-7

PROJECT SITE 6, BAKER DAMDATE May 16, 1979PROJECT FEATURE Outlet Works - SpillwayNAME D. LaGatta, C. OsgoodDISCIPLINE Structural/Hydraulic/GeotechnicalNAME S. Mazur, G. Slaney

AREA EVALUATED	CONDITION
<u>OUTLET WORKS - SPILLWAY WEIR, APPROACH AND DISCHARGE CHANNELS</u>	
a. Approach Channel	Outlet structure and spillway are one
General Condition	
Loose Rock Overhanging Channel	None observed
Trees Overhanging Channel	
Floor of Approach Channel	
b. Weir and Training Walls	
General Condition of Concrete	Spillway structure consists of two elements, an overflow with low and high stages of control and open sluiceway type discharge channel. The spillway structure appeared to be in good condition.
Rust or Staining	None
Spalling	None
Any Visible Reinforcing	
Any Seepage or Efflorescence	Efflorescence at spillway training wals.
Drain Holes	Clear and operating
c. Discharge Channel	
General Channel Condition	Clear
Loose Rock Overhanging Channel	None
Trees Overhanging Channel	None-Downstream the channel enters woods
Floor of Channel	Rocky; riprap extends about 30 feet
Other Obstructions	None

PERIODIC INSPECTION CHECK LIST

PROJECT SITE 6, BAKER DAMDATE May 16, 1979PROJECT FEATURE Service Bridge

NAME _____

DISCIPLINE _____

NAME _____

AREA EVALUATED

CONDITION

OUTLET WORKS - SERVICE BRIDGE

a. Super Structure

This facility has no service bridge.

Bearings

Anchor Bolts

Bridge Seat

Longitudinal Members

Under Side of Deck

Secondary Bracing

Deck

Drainage System

Railings

Expansion Joints

Paint

b. Abutment & Piers

General Condition of Concrete

Alignment of Abutment

Approach to Bridge

Condition of Seat & Backwall

APPENDIX B

ENGINEERING DATA

1. LIST OF DESIGN, CONSTRUCTION AND MAINTENANCE RECORDS
2. PAST INSPECTION REPORTS
3. PLAN AND DETAILS

AVAILABLE ENGINEERING DATA

1. A set of drawings (20 sheets), dated June 1969, showing as built plans and details of the dam and appurtenant structures.
2. Design Data: including layout, hydraulic design, geology and soils reports, structural design, quantities and specifications.
3. Construction Data: including as-built plans, job diaries, surveying records, test drilling logs, compaction test results, concrete tests, and certificate of completion.

All of the above are on file with the U.S.D.A. Soil Conservation Service, Federal Building, Durham, N.H. 03824.

PAST INSPECTION REPORTS

*FILED IN 247.11
63-300.*

UNITED STATES DEPARTMENT OF AGRICULTURE
SOIL CONSERVATION SERVICE

Federal Building, Durham, New Hampshire 03824

September 25, 1978

Mr. George M. McGee, Sr., Chairman
New Hampshire Water Resources Board
37 Pleasant Street
Concord, New Hampshire 03301

G. M. McGee Sr.

Dear George:

In regard to the Baker River Watershed Site 6, we are concerned about the deterioration of the box concrete and the lack of drainage on the right abutment. We plan to investigate these conditions early next summer and will forward our recommendations then.

Sincerely,

Charles H. Dingle

Charles H. Dingle
Assistant State Conservationist (WR)



State of New Hampshire

WATER RESOURCES BOARD

37 Pleasant Street
Concord, N.H. 03301

TELEPHONE 271-1225

September 18, 1978

Mr. Keith MacPherson
Soil Conservation Service
Federal Building
Durham, New Hampshire 03824

Dear Mr. MacPherson:

This letter is to inform you of the prevailing conditions at two of the Baker River System Flood Control Sites.

Site No. 6 249-1

- 1- Trash racks have been cleared of debris.
- 2- All bushes and tree sprouts on the dam have been pulled, cut or sprayed.
- 3- The concrete is still spalled in several areas of the channel wall and has broken away from the railing posts. The Board feels that it is your agency's responsibility for this repair.
- 4- To date we have not received your agency's recommendation of corrective action regarding the ponding against the right bank channel wall for our review. During this year's inspection this item was of some concern to Ray Winner.
- 5- The traffic signs and riprap have been removed from the outlet channel.

Site No. 11-A 249-14

- 1- The bushes and tree sprouts on the dam and in the emergency spillway have been pulled, cut or sprayed.
- 2- The roadway guardrail repair is to be completed by the Town and not by us.

A more complete report will follow indicating all the work accomplished this year with respect to this year's O & M maintenance field inspection reports.

Very truly yours,

George McGee Sr.
George M. McGee, Sr.,
Chairman

GMM:GLK:paf

MAINTENANCE CHECKLIST FOR PL 566 FLOOD CONTROL STRUCTURES

This maintenance checklist is a guide for determining the maintenance required for Public Law 566 flood control structures in New Hampshire. It doesn't take the place of experience and judgment and is not inclusive. Items of a difficult nature to check, such as principal spillway conduit condition, are not included. Intensive checks of these items are necessary at proper intervals. Review of ☒ Built drawings, the design folder, structure history, and previous maintenance reports should be part of the inspection. Prompt maintenance is a vital part of safe and effective operation.

Except where otherwise indicated, completion of this form may be facilitated by ranking maintenance items on a 1 to 4 basis where

- 1 = satisfactory
- 2 = satisfactory, but check carefully at next inspection
- 3 = requires maintenance this season
- 4 = requires immediate attention.

249.01

WATERSHED <u>Baker</u>	SITE <u>6</u>	DATE <u>6-13-78</u>
INSPECTED BY <u>Gary Kerr, Lyall Milligan (WRB); Mike Dannehy, Nick Luhtala, Ray Wenninger</u>		
(SES)		

1. GENERAL ITEMS

Access Road.	N/A
Site Fencing.	1
Traffic Conditions.	1
Vandalism Control.	(3)
Trash Control.	

COMMENTS Traffic signs and riprap in box. These should be removed as they could affect flow distribution.

2. RESERVOIR

Timber stand at reservoir.	1
Debris and slash.	3 ✓
Sediment level in relation to low stage inlet	

COMMENTS A little debris at trash rack should be removed.

3. EMBANKMENT AND EXCAVATED SLOPES

(Report riprap and vegetation and erosion condition under Items 4 and 5.)

	<u>Dam</u>	<u>Dike</u>	<u>Emergency Spillways</u> <u>left</u> <u>right</u> ^{1/}		<u>Other</u> <u>()</u> <u>()</u>	
Sliding or sloughing	<u>1</u>	<u>—</u>	<u>—</u>	<u>—</u>	<u>—</u>	<u>—</u>
Holes (rodent and other) (check especially at embankments)	<u>1</u>	<u>—</u>	<u>—</u>	<u>—</u>	<u>—</u>	<u>—</u>
Excessive settlement (embankments)	<u>1</u>	<u>—</u>	<u>—</u>	<u>—</u>	<u>—</u>	<u>—</u>
Cracks						
Traverse	<u>1</u>	<u>—</u>	<u>—</u>	<u>—</u>	<u>—</u>	<u>—</u>
Longitudinal	<u>—</u>	<u>—</u>	<u>—</u>	<u>—</u>	<u>—</u>	<u>—</u>
Seepage ^{2/}	<u>1</u>	<u>—</u>	<u>—</u>	<u>—</u>	<u>—</u>	<u>—</u>
Piping ^{2/}	<u>1</u>	<u>—</u>	<u>—</u>	<u>—</u>	<u>—</u>	<u>—</u>

COMMENTS _____

4. RIPRAP

	<u>Displ. of Rock</u>	<u>Loss of Spalls</u>	<u>Loss of Bedding</u>	<u>Erosion of Found.</u>	<u>Break- down of Rock</u>
Dam					
Upstream berm	<u>4</u> ✓	<u>4</u> ✓	<u>1</u>	<u>4</u> ✓	<u>1</u>
Principal Spillway Outlet	<u>—</u>	<u>—</u>	<u>—</u>	<u>—</u>	<u>—</u>
Embankment Gutters					
left	<u>—</u>	<u>—</u>	<u>—</u>	<u>—</u>	<u>—</u>
right	<u>—</u>	<u>—</u>	<u>—</u>	<u>—</u>	<u>—</u>
Emergency Spillway					
location _____	<u>—</u>	<u>—</u>	<u>—</u>	<u>—</u>	<u>—</u>
location _____	<u>—</u>	<u>—</u>	<u>—</u>	<u>—</u>	<u>—</u>
Waterways					
location _____	<u>—</u>	<u>—</u>	<u>—</u>	<u>—</u>	<u>—</u>
location _____	<u>—</u>	<u>—</u>	<u>—</u>	<u>—</u>	<u>—</u>
Outlet Channel	<u>—</u>	<u>—</u>	<u>—</u>	<u>—</u>	<u>—</u>
Other _____	<u>—</u>	<u>—</u>	<u>—</u>	<u>—</u>	<u>—</u>

COMMENTS Rock riprap should be replaced on each side of box as soon as possible
as flow could erode impervious blanket below riprap if the riprap is not
satisfactory. The correct size should be used for the total layer thickness,
not just put back on top of the existing rock. Fines washed into the riprap
on the right side could increase frost loading on the box sidewall.

VEGETATION

	Dam	Emergency Spillways ^{1/}		Dike	Outlet Channel	Water way	Other (at right side of box)
Condition of stand (including need for lime and fertilizer)	<u>1</u>	—	—	—	—	—	—
Undesirable vegetation	<u>1</u>	—	—	—	—	—	—
Drainage (surface)	<u>1</u>	—	—	—	—	—	<u>3</u>
Erosion ^{2/}	<u>1</u>	—	—	—	—	—	—
Sedimentation	<u>1</u>	—	—	—	—	—	—
Condition of planting	<u>1</u>	—	—	—	—	—	—
Pest control	<u>1</u>	—	—	—	—	—	—
Fire control	<u>1</u>	—	—	—	—	—	—

COMMENTS All vegetation o.k. Drainage from right side area of box should
be diverted from box. This could increase frostloads on box and increase
frost related cracking of concrete. An average of 4" of water ponded
against box sidewall.

EMBANKMENT, STRUCTURAL, & OTHER DRAINS

		Dam ^{1/}		Other	
		left	right	()	()
Depth of Flow	With any obstruction	<u>3/</u>	<u>3/</u>	—	—
(in inches above invert)	Without any obstruction	—	—	—	—
Turbidity of Discharge	With any obstruction	—	—	—	—
(yes, no)	Without any obstruction	—	—	—	—
Condition of Protective	Outside	—	—	—	—
Coating	Inside	—	—	—	—
Obstruction in Flow		—	—	—	—
(yes, no)		—	—	—	—
Animal Guard Condition		<u>1</u>	<u>1</u>	—	—
Outlet Condition		<u>1</u>	<u>1</u>	—	—
Retarding Pool Elevation (ft. msl)	_____ or <u>6 in. (ft.)</u> above _____ below <u>LS</u>				
Other	_____				

COMMENTS ^{3/}Submerged drains. Drain outlets into box appear o.k. Water over
sill so close inspection not possible at this time. Recommend checking
thoroughly drain outlet condition during low water.

RISER

N/A

Caution Be extremely careful when using ladders. Check condition before using. Ladders are sometimes broken, loose, corroded, and or slippery.
Use safety harness.

Ladders:
 inside and out

Condition of protective coating___;
 Corrosion___; Damaged parts___; Loose___;
 Other___.

Concrete:
 inside and out

Cracking___; Spalling___; Other deterioration___;
 Excessive movement (check joint at riser and conduit)___; Other___.

Trashracks:
 low and high stage

Condition of protective coatings___; Corrosion___;
 Damaged parts___; Condition of fastenings___;
 Need of gratings due to beaver___; Safety condition (protruding fastenings, sharp edges, etc.)___; Other___.

Manhole:

Condition of protective coatings___; Corrosion___;
 Damage___; Lock operable___; Other___.

Gate:
 including lifting device, stem, guides, disc

Condition of protective coating___; Corrosion___;
 Damaged parts___; Condition of fastenings___;
 Stem alignment___; Lubrication___; Operation___; Other___.

Safety Items:

Condition of warning signs___; Condition of safety equipment___; Other___.

COMMENTS

(specify) BOX INLET

Cracking 3; Spalling 1; Other deterioration
3; Excessive movement (check joints) 1;
Waterstops 1; Joint sealant 1; Other .

Condition of protective coatings 1; Corrosion 1; Damaged parts 1; Condition of fastenings 1; Need of gratings due to beaverno 0; Safety condition (protruding fastenings, sharp edges, etc.) 1; Other 0.

Condition of protective coating___; Corrosion___; Damaged parts___; Condition of fastenings___; Stem alignment___; Operation___; Lubrication___; Wood decay___; Other___.

Report under "Embankment and Other Drains"

Condition of protective coating 1; Corrosion 1; Damaged parts 3; Condition of Fastenings ; Wood decay ; Safety condition (protruding fastenings, sharp edges, etc.)
; Other .

Condition of warning signs___; Condition of
safety equipment ; Other .

COMMENTS Need to put sealer in three or so fence sockets. Concrete box does
not appear to be cracking anymore than before. However, a protective
sealer such as silicone may retard water and freezing damage.

[illegible]

COMMENTS

MAINTENANCE CHECKLIST FOR PL 566 FLOOD CONTROL STRUCTURES

Maintenance checklist is a guide for determining the maintenance required Public Law 566 flood control structures in New Hampshire. It doesn't take place of experience and judgment and is not inclusive. Items of a difficult are to check, such as principal spillway conduit condition, are not included. nsive checks of these items are necessary at proper intervals. Review of built drawings, the design folder, structure history, and previous maintenance orts should be part of the inspection. Prompt maintenance is a vital part of and effective operation.

pt where otherwise indicated, completion of this form may be facilitated ranking maintenance items on a 1 to 4 basis where

- 1 = satisfactory
- 2 = satisfactory, but check carefully at next inspection
- 3 = requires maintenance this season
- 4 = requires immediate attention.

ERSHED ROKER RIVER SITE 6 DATE 5-20-77
 ECTED BY KERR DANNENY LUHTALA
MILLIGAN KELSEY MARCHERSON

GENERAL ITEMS

Access Road.	<u>1</u>
Site Fencing.	<u>2</u>
Traffic Conditions.	<u>1</u>
Vandalism Control.	<u>3</u>
Trash Control.	<u>3</u>

COMMENTS MANY ROCKS FROM RIPRAP ALONG SIDES
OF BOX HAVE BEEN THROWN INTO BOX INLET.
CONSIDERATION MAY NEED TO BE GIVEN TO EITHER
INCREASING THE SIZE OF THE RIPRAP OR GROUTING
THE RIPRAP.
THERE IS A CONSIDERABLE AMOUNT OF GRASS GROWTH
IN THE TRASH RACK

RESERVOIR

Timber stand at reservoir.	<u>1</u>
Debris and slash.	<u>1</u>
Sediment level in relation to low stage inlet	<u> </u>

COMMENTS _____

3. EMBANKMENT AND EXCAVATED SLOPES

(Report riprap and vegetation and erosion condition under Items 4 and 5.)

	Dam	Dike	Emergency Spillways ^{1/}		Other	
			left	right	()	()
Sliding or sloughing	<u>1</u>	—	—	—	—	—
Holes (rodent and other) (check especially at embankments)	<u>1</u>	—	—	—	—	—
Excessive settlement (embankments)	<u>1</u>	—	—	—	—	—
Cracks						
Traverse	<u>1</u>	—	—	—	—	—
Longitudinal	<u>1</u>	—	—	—	—	—
Seepage ^{2/}	<u>1</u>	—	—	—	—	—
Piping ^{2/}	<u>1</u>	—	—	—	—	—

COMMENTS _____

4. RIPRAP

	Displ. of Rock	Loss of Spalls	Loss of Bedding	Erosion of Found.	Break- down of Rock
Dam					
Upstream berm	<u>3</u>	<u>3</u>	—	<u>1</u>	<u>1</u>
Principal Spillway Outlet	—	—	—	—	—
Embankment Gutters					
left	—	—	—	—	—
right	—	—	—	—	—
Emergency Spillway					
location _____	—	—	—	—	—
location _____	—	—	—	—	—
Waterways					
location _____	—	—	—	—	—
location _____	—	—	—	—	—
Outlet Channel	<u>1</u>	<u>1</u>	—	<u>1</u>	<u>1</u>
Other _____	—	—	—	—	—

COMMENTS MANY PIECES OF ROCK RIPRAP HAVE BEEN
REMOVED FROM THE SIDE OF THE STRUCTURE &
DROPPED INTO THE BOX. CONSIDERATION SHOULD
BE GIVEN TO GRADING THE ROCK OR REPLACING
IT WITH LARGER ROCK TO PREVENT FURTHER
REMOVAL.

^{1/}Looking downstream.

^{2/}Check especially at downstream face of embankments.

5. VEGETATION

	Dam	Emergency Spillways		Dike	Outlet Channel	Water way	Other ()
		left	right ^{1/}				
Condition of stand (including need for lime and fertilizer)	<u>1</u>	—	—	—	<u>NA</u>	—	—
Undesirable vegetation	<u>3</u>	—	—	—	<u>1</u>	—	—
Drainage (surface)	<u>NA</u>	—	—	—	<u>NA</u>	—	—
Erosion ^{2/}	<u>1</u>	—	—	—	<u>1</u>	—	—
Sedimentation	<u>1</u>	—	—	—	<u>1</u>	—	—
Condition of planting	<u>NA</u>	—	—	—	<u>NA</u>	—	—
Pest control	—	—	—	—	—	—	—
Fire control	—	—	—	—	—	—	—

COMMENTS SOME BRUSH CONTROL NEEDED ON DAM.

TRIFOLIUM - REED CANARY

6. EMBANKMENT, STRUCTURAL, & OTHER DRAINS

		Dam		Other	
		left	right ^{1/}	()	()
Depth of Flow (in inches above invert)	With any obstruction	<u>3</u>	<u>4</u>	—	—
	Without any obstruction	<u>3</u>	<u>3</u>	—	—
Turbidity of Discharge (yes, no)	With any obstruction	<u>NO</u>	<u>NO</u>	—	—
	Without any obstruction	<u>NO</u>	<u>NO</u>	—	—
Condition of Protective Coating	Outside	<u>2</u>	<u>2</u>	—	—
	Inside	<u>2</u>	<u>2</u>	—	—
Obstruction in Flow (yes, no)		<u>NO</u>	<u>NO</u>	—	—
Animal Guard Condition		<u>1</u>	<u>1</u>	—	—
Outlet Condition		<u>1</u>	<u>1</u>	—	—
Retarding Pool Elevation (ft. msl) _____ or _____ (ft.)				above	below
Other _____					

COMMENTS OUTLETS PARTIALLY SUBMERGED

^{1/}Looking downstream.

^{2/}Including wave, surface, stream, manmade, and livestock erosion.

RISER

Caution Be extremely careful when using ladders. Check condition before using. Ladders are sometimes broken, loose, corroded, and or slippery.
Use safety harness.

Ladders:
inside and out

Condition of protective coating___;
Corrosion___; Damaged parts___; Loose___;
Other___.

Concrete:
inside and out

Cracking___; Spalling___; Other deterioration___;
Excessive movement (check joint at riser and conduit)___; Other___.

Trashracks:
low and high stage

Condition of protective coatings___; Corrosion___;
Damaged parts___; Condition of fastenings___;
Need of gratings due to beaver___; Safety condition (protruding fastenings, sharp edges, etc.)___; Other___.

Manhole:

Condition of protective coatings___; Corrosion___;
Damage___; Lock operable___; Other___.

Gate:
including lifting device, stem, guides, disc


Condition of protective coating___; Corrosion___;
Damaged parts___; Condition of fastenings___;
Stem alignment___; Lubrication___; Operation___; Other___.

Safety Items:

Condition of warning signs___; Condition of safety equipment___; Other___.

COMMENTS

COMMENTS





LEGEND
 INDICATES LOCATION WHERE PHOTO
 WAS TAKEN AND DIRECTION

NOTE:
 PHOTO 21 TAKEN 3000 FT UPSTREAM

PLAN

SITE NO. 6
 BAKER FLOODWATER
 RESERVOIR

[illegible][illegible]

APPENDIX C

PHOTOGRAPHS

FOR LOCATION OF PHOTOS, SEE FIGURE 1
LOCATED IN APPENDIX B




PHOTO NO. 1 - Dam and spillway as viewed from right bank of reservoir.



PHOTO NO. 2 - Upstream face of left dam embankment.



PHOTO NO. 3 - View of left abutment, reservoir is in background.



PHOTO NO. 4 - Upstream side of right embankment of the dam.



PHOTO NO. 5 - Crest of dam
from left abutment.




PHOTO NO. 6 - Crest of dam from right abutment.




PHOTO NO. 7 - View of spillway section looking upstream.




PHOTO NO. 8 - Spillway section through embankment.




PHOTO NO. 9 - Right upstream wall of spillway.




PHOTO NO. 10 - Left upstream wall of spillway.




PHOTO NO. 11 - View of right wall of spillway at embankment.




PHOTO NO. 12 - Upstream end of spillway from the right reservoir bank.



PHOTO NO. 13 - View of upstream end of spillway from the left reservoir bank.




PHOTO NO. 14 - Detail of trash rack.




PHOTO NO. 15 - Left drain outlet pipe downstream of the spillway.



PHOTO NO. 16 - Right drain outlet pipe downstream of the spillway.



PHOTO NO. 17 - Erosion adjacent to the right side of the spillway.



PHOTO NO. 18 - Drainage on the right abutment adjacent to the spillway, looking upstream.



PHOTO NO. 19 - Close-up of
drainage on right abutment.



PHOTO NO. 20 - Drainage of right abutment.



PHOTO NO. 21 - Constriction in reservoir located 3000 feet upstream of the dam.



PHOTO NO. 22 - Channel downstream of the dam.

APPENDIX D
HYDROLOGIC AND HYDRAULIC COMPUTATIONS

4NTB

Made by

RY

Date

7/2/79

Job No

5965-11-03

Checked by

HM

Date

7/23/79

Sheet No.

1

For Baker Dam Site #6

HYDRAULICS & HYDROLOGY

Baker Dam Site 6 is Located across Pond Brook
in the Town of Wentworth, N.H. in the Merrimack
River Basin

Classification

Size: Intermediate

Hazard: Significant

Basic Data

Drainage Area = 16.96 Sq mi

Basin upstream storage in Upper Baker Pond
10.00 sq mi controlled

6.96 sq mi direct to Lower Baker

Surface area Upper Baker Pond

Average stream bed slope 400 ± 1 mi

Reservoir Area

Normal pool Elev. 894 ft MSL

Storage 210 acre ft

Max. (Top of Dam) Elev. 906 ft MSL

Storage 2240 acre ft

Crest Emer. Spillway elev 900.0

Storage 921 acre ft

Dam: Earth

Length 203 ft

Height 13 ft

Spillways

Low Level - crest elev 894.0

Length 360 ft.

High Level - crest elev 900.0

Length 154.0 ft.

See Appendix "B" for plan of Dam

HNTB JWARD NEEDLES TAMMEN & BERGENDOFF	Made by	RY	Date	8/20/79	Job No.	5965-11-03
	Checked by	JM	Date		Sheet No.	2
For Baker 6						

Step 1 Calculation of Test Flood Inflow

Classification Size: Intermediate
Hazard: Significant

Hydrologic Evaluation Guideline recommends

1/2 to full PMF for inflow

Use 1/2 PMF as size classification is on lower end of classification range of 1000 acre-ft to 50000 acre-ft vs 2240 acre-ft

Runoff PMF = 19 in

1/2 PMF runoff equals 9.5 inches.

60% of the basin runoff passes through Upper Baker Pond with a surface area of 247 acres at elev. 910 and a corresponding storage of 1662 acre-ft.

Enough storage is provided to reduce the peak flows from the 10.0 sq mile area, and offset the peak from the 6.96 sq mile area peak.

SES calculations indicate the peak flow from the 10 sq mile area to Upper Baker Pond to be 4607 cfs and the peak from the 6.96 square mile area directly tributary to Lower Baker Pond to be 4976 cfs. Routing from Upper Baker Pond and adding the routed hydrograph from the 10.0 sq mile area to the hydrograph from the 6.96 sq mile area produces a peak inflow at Baker Site 6 of 5120 cfs.

HN TB OWARD NEEDLES TAMMEN & BERGENDOFF	Made by <i>RY</i>	Date <i>1/31/79</i>	Job No <i>5465-11-03</i>
	Checked by <i>HM</i>	Date	Sheet No <i>3</i>
For <i>Site # 6</i>			

This is a complex drainage basin the Test Flood inflow is calculated using the SCS computations adjusted by a factor to obtain a test flood equivalent to the $1/2$ PMF.

SCS calcs Peak inflow to Site 6 5120 cfs
 Runoff 4.27 in for 6.96 sq mi
 4.06 in for 10.0 sq mi.

$$\begin{array}{rcl}
 \text{weighted ave} & 4.27 \times 6.96 = 29.72 & \\
 & 4.06 \times 10.00 = 40.60 & \\
 & \hline
 & 16.96 & 70.32 \\
 & & \hline
 & & 70.32 / 16.96 = 4.15 \text{ in}
 \end{array}$$

Runoff equals 4.15 in

Test Flood Runoff = 7.5 in

therefore Test Flood inflow

$$\frac{7.5}{4.15} \times 5120 \text{ cfs} = 11720 \text{ cfs say } 11700 \text{ cfs}$$

SCS Flood Hydrographs and Routed Hydrographs are in appendix following this section.

For Baker #6

Step 2 Calculation of Inflow Surge

Stage - Discharge Curve

Elev	ft above High Stage	A Low Stage Flow, orifice	B High Stage Flow	C Crest of Dam	Total
994.0	0	0			0
900.0	0	293 cfs			293 cfs
901.0	1	226	337 cfs		563
902.0	2	219	1076		1295
903.0	3	213	2136		2349
904.0	4	*	3384		3384
905.0	5		3785		3785
906.0	6		4200		4200
907.0	7		4629	541 cfs	5170
908.0	8		5071	1529	6600
909.0	9		5389	2210	8199
910.0	10		5996	4326	10322

* Spillway discharge channel width controls flow from both Low and high stage crest.

A. From Baker River #3, Design Book, SCS, Durham, N.H.
See copies of calcs. at the end of this section

B. Same as above calculations extended above elev. 904.0

C. Computed as flow over broad crest weir

$$Q = CLH^{3/2}$$

$$C = 3.09$$

$$L = 203 \text{ ft overall} - 28 \text{ ft spillway width} = 175'$$

$$H = \text{ft above dam crest}$$

$$Q = 540.75 \times H^{3/2}$$

See Figure 2 for Plot.

Step 3 Estimate of Surge - Storage Effect

$$Q_{P1} = 11,700 \text{ cfs}$$

$$\text{Runoff} = 9.5 \text{ in}$$

$$Q_{P2} = Q_{P1} \times \left(1 - \frac{\text{Stor}}{95''}\right)$$

Stor in acre-ft read from Figure 1 - 210 acre-ft

$$\text{Stor (in)} = \frac{\text{Stor (acre-ft)} \times 12 \text{ in/ft}}{16.96 \text{ sq mi} \times 640 \text{ acre/mi}^2} = (.00111) (\text{Stor acre-ft})$$

Routing Curve


See Fig 2 for Plot


Elev	Stor acre-ft	Stor (in)	Q_{P2}
950	711	.79	10700 cfs
923	1315	1.46	9900
906	2030	2.25	8900
908	2490	2.76	8300
910	2950	3.27	7670

From Figure 2

Outflow 8000 cfs

Stage = 908.8
or 2.8 ft over dam crest





STAGE-DISCHARGE
CURVE
LAKE DAM #6
1965-11-03

DISCHARGE = 1200 (cfs)

Downstream Damage Estimation

Step 1 Reservoir Storage

Top of dam 2240 acre-ft Lower Baker Pond
elev 906.00 only.

Step 2 Peak Outflow

$$\text{Breach } Q = 8/27 \sqrt{g} (40\%) W_b \cdot Y_o^{3/2}$$

$W_b = 40\%$ of dam width = .40 (175)
not including spillway section 28 ft wide

$Y_o =$ Total height stream to pool elev. 12 ft (12 ft above crest)


$$Q_B = 8/27 (5.67) (.40) (175) (12)^{3/2} = 4190 \text{ cfs}$$

Spillway Discharge at top of dam 4200 cfs

$$Q_{P_1} = 9090 \text{ cfs}$$

$$\text{Say } 9100 \text{ cfs}$$

Step 3 Stage-Discharge



$$\text{Reach} = 16,000 \text{ ft}$$

$$S = .0189\%$$

$$n_{\text{channel}} = .04$$

$$n_{\text{overbank}} = .08$$

Stage-Discharge

5 ft	3260 cfs
6 ft	4660
7	6300
8	8180
9	10310

Step 4 Reach Outflow

Reach 1 1000 ft long.

$S = 2240$ acre ft


$Q_{P1} = 9100$ cfs Stage 8.45 ft $area = 516$ acre ft

$$V_1 = \frac{516 \times 1000 \text{ ft}}{43560} = 12 \text{ acre ft}$$

no reduction in outflow due to small channel storage

Step 3 Reach 2 Stage Discharge

$n_{ob} = .08$ $n_{ch} = .04$
 $TW = 20'$



Reach = 15000 ft

$S = .0129'$

$n_{ch} = .04$

$n_{ob} = .08$

Stage - Discharge

5 ft	822 cfs
7	1710
9	3410
11	5770
13	7570

Step 4 Reach Outflow

$Q_{P1} = 9100$ cfs Stage₁ = 12.7 ft $area_1 = 822$ acre ft

$$V_1 = \frac{822 \times 15000}{43560} = 283 \text{ acre ft} < \frac{2240}{2} \text{ reach ok}$$

$$Q_{P2} = 7100 \text{ cfs} \left(1 - \frac{283}{2240}\right) = 7750 \text{ cfs}$$

Stage₂ = 12.15 ft $area_2 = 729$ acre ft

$$V_2 = \frac{729 \times 15000}{43560} = 251 \text{ acre ft}$$

HNTB

Made by

RY

Date

6/25/79

Job No.

5965-11-03

Checked by

-M

Date

7/23/79

Sheet No.

8

For

Baker #6

 $V_{ave} = 267 \text{ acre ft}$

$$Q_{P2} = 9100 \text{ cfs} \left(1 - \frac{267}{2240} \right) = 8015 \text{ cfs}$$

$$Stage = 12.2 \text{ ft}$$

HNTB

Made by

RY

Date

6/25/79

Job No

5965-11-03

Checked by

-1-

Date

7-22-1-0

Sheet No

9

For

32ker # 6

SummaryDownstream stage prior to breach of dam
Reach 2

9.6 ft

Subsequent to breach of Dam
at dam

8.45 ft

1000 ft d.s. note: 18 ft drop in channel
thru reach

12.7 ft

16000 ft d.s.

12.2 ft

PROPORTIONAL ERROR (%)

13

12

11

10

9

8

7

6

5


Reach 2


Reach 1

STEADY DISCHARGE
CURVE
DRAIN BASIN
3450-40
5755-63

Discharge (cfs)

2000 4000 6000 8000 10000 12000





NATIONAL PROGRAM OF INSPECTION OF
NON FEDERAL DAMS

BAKER RIVER DAM SITE 6
POSSIBLE FLOOD DAMAGE AREA

Wentworth, N.H.
USGS Quad. Warren, N.H.

Scale 1:24,000
0 100 200
FEET

State	NH	Project	BAKER RIVER SITE 6		
By	RW	Date	2-69	Checked By	Date
Subject				WORK PLAN - DESIGN COMPARISON	Job No
				Sheet	1 of 42

ITEM	UNIT	WORK PLAN	DESIGN	COMMENTS
DRAINAGE AREA	SQ. MI.	16.96	16.96	
SEDIMENT CAPACITY				
SEDIMENT UNCOMPACTED	AC. FT.	210	210	
BENEFICIAL	AC. FT.	0	0	
RETARDING	AC. FT.	1200	1194	
TOTAL	AC. FT.	1410	1404	
DIFFERENCE HIGH & LOW S	AC. FT.	925	921	
SEDIMENT AREA				
SEDIMENT POOL	ACRE	-	-	
RETARDING POOL	ACRE	183	183	INCLUDES PRESENT POND
DESIGN HIGH WATER	ACRE			
VOLUME OF FILL	CU. YD.	(CONC.)		
TOP OF DAM ELEV.	FEET	900.0	906.0	CONC. DAM IN V.D.P.
MAX. HEIGHT OF DAM	FEET	10	~ 13	BOX INLET USED IN DESIGN
EMERGENCY SPILLWAY				
CREST ELEVATION	FEET	900.0	900.0	
BOTTOM WIDTH	FEET	150	154	
TYPE	-	CONC. DAM	BOX INLET	
PERCENT CHANCE OF USE	-	10	10	
SP. CURVE NO. CONC. D	-	70	70	
EMERGENCY HYDROGRAPH				
STORM RAINFALL - 6 HR.	IN.	7.0	7.0	
STORM RUNOFF	IN.	2.83	2.83	
VELOCITY OF FLOW - V	FPS	-	-	
PEAK DISCHARGE RATE	CFS	865	890	
MAX. WATER SURFACE EL.	FEET	901.5	901.5	
FEEDBOARD HYDROGRAPH				
STORM RAINFALL - 6 HR.	IN.	8.75	8.75	
STORM RUNOFF	IN.	4.14	4.14	
VELOCITY OF FLOW - V	FPS	-	-	
PEAK DISCHARGE RATE	CFS	2140	2000	
MAX. WATER SURFACE EL.	FEET	902.9	902.7	
PRINCIPAL SPILLWAY				
RIVER SIZE	FT.	-	-	
MAX. LOW STAGE FLOW	CFS	293	293	
ORIFICE SIZE	FT. ²	18.9	18.33	
MAX. HIGH STAGE FLOW	CFS	0	0	
PIPE SIZE	DIA.	-	-	
CAPACITY EQUIVALENTS				
TOTAL SEDIMENT VOL.	IN.	0.23	.23	
RETARDING STORAGE	IN.	1.33	1.32	
EM. SPILLWAY STORAGE				
TO TOP OF DAM	IN.	.53	> .53 *	* TO TOP OF DAM
CLASS OF STRUCTURE	-	b	b	
CONSTRUCTION COSTS	-	\$12,382		

Stoie

NIH

Project

BAKER KILVER

$$E_y$$

P.M.

Cote

7-69

Checked By

Date _____

Job No

NH-631-1

Subject

STAGE - STORAGE DATA

Sheet

21

47

LOWER POND

ELEV.	DIFFERENCE IN ELEV.	AREA FLOODED		AVERAGE AREA ACRES	INTERVAL STORAGE AC. FT.	TOTAL STORAGE	
		IN ²	ACRES			AC IN.	AC FT.
893.3			118.57				118.57
	0.2*			119.75*	24*		
894.0	(CPEST)*		120.93*				0*
	2.0*			122.74	265		
896.0			144.54				265*
	4.0			163.95	656		
900.0			183.36				921*
	2.0			192.04	384		
902.0			200.73				1305*
	2.0			215.36	(431)		
904.0			(230)EST.				1736*
ALL DATA EXCEPT (*) TAKEN FROM "STAGE-STORAGE (LOWER POND)" SHEET IN WORK PLAN DATA BY J.H.O. 10-23-62							
* FLOOD FLOWING							

ALL DATA EXCEPT (3) TAKEN FROM
"STAGE - 2 (LOW POND)" SHEET
IN WORK PLAN DATA BY J.H.O. 10-23-62

* 1	1000	1000
-----	------	------

BAKER RIVER SIG HEADWALL) 20 of 42

HYDRAULIC DESIGN TRAPEZOIDAL WEIR)

HEAD	0.5	0.75	1.0	2.75	4.0		
CONTROL	AT	INLET					
H/W	.0192	.0288	.0285	.144	.154		
Wc	167	167	167	169	169		
Wc/L	1.08	1.08	1.08	1.11	1.10		
CORR. FOR							
HEAD	.76	.76	.76	.91	.91		
SHAPE	.95	.95	.95	.95	.95		
CHANNEL	.86	.86	.86	.87	.87		
DIKE							
CORRECTED CORR. X T ₂	2.130	2.130	2.130	2.580	2.580		
H ^{3/2}	.354	.650	1.000	7.262	8.000		
Q _{RECT}	116	213	328	2335	3179		
H ^{5/2}	.177	.477	1.000	27.23	32.00		
Q _{TRAP}	2	4	9	245	288		
Q _{WEIR TOT.}	118	217	337	3130	3467		
CONTROL	AT	HEAD					
H ₀₂	7.93	7.93	7.93	7.93	7.93		
H + H ₀₂	7.43	9.62	7.93	12.68	12.93		
(H + H ₀₂) ^{3/2}	22.96	30.12	31.29	45.15	46.49		
Q _{HEADWALL}	2108	3192	2272	3227	3384		
ELEV.	900.5	903.75	901.0	903.75	904.0		
Q _{WEIR TOT.} = Q _{RECT} + Q _{TRAP} + 8/15 TAN 4/3 T ₂ = 9							
E/W = 2.46							
Q _{HEADWALL} = C ₂ W T ₂ ^{3/2} (
D/W = .37							

BAKER RIVER SITE 6

HYDRAULIC DESIGN BOX INLET

HIGH STAGE ORIFICE FLOW

SHT 23 OF 42

$$Q = (.6)(18.33)(8.02)(H)^{1/2} \quad (.6) \text{ COEFF USED AS HEAD IS UNCERTAIN DUE TO FLOW IN BOX}$$

(1) ELEV. LOWER POND	(2) $Q_{WIR(HS)}$	(3) $Q_{ORIFICE}$ (ASSUMED)	(4) Q_{TOTAL} (ASSUMED)	(5) ELEV. WATER IN BOX (Q_{COL4})	(6) $H_{ORIFICE}$ COL (1)(5)	(7) $Q_{ORIFICE}$ FOR H IN COL(6)		
900.5	118	225	343	893.95	6.55	226		
900.75	217	225	442	894.3	6.45	224		
901.0	337	223	560	894.5	6.50	225		
901.25	480	225	705	894.8	6.45	224		
901.5	658	225	823	895.1	6.40	223		
901.75	855	222	1077	895.5	6.25	221		
902.0	1076	220	1296	895.85	6.15	219		
902.25	1320	220	1540	896.2	6.05	217		
902.5	1590	215	1805	896.55	5.95	215		
902.75	1865	210	2075	896.85	5.90	214		
903.0	2136	210	2346	897.15	5.85	213		
903.25	2447	210	2657	897.45	5.90	212		
903.5	2773	210	2963	897.75	5.75	211		
903.75	3130	210	3340	898.05	5.70	211	WILL BE	LESS AS
904.0	3384	210	3594	898.3	5.70	211	HEADS	CONSIDER

BAKER RIVER SITE 6

NH-681-H

L = 36'

LOW STAGE WEIR FLOW

SHT 24 OF 42

ELEV. W.S. UPST.	H	H/W W=26'	H/W CORR.	CORRECTED C, $\sqrt{2g}$	$H^{3/2}$	$Q_{WEIR(C)}$ FREE FLOW	$Q_{CORR(F)}$ (FEET/SEC)	$Q_{WEIR(LIC)}$ ACTUAL
894.0 (CREST)								
.2	.2	.007	.76		.0894	9	20	9
.4	.4		.76		.2530	24	173	24
.6	.6		.76		.4648	45	127	45
.8	.8		.76		.7155	69	144	69
895.0	1.0	.038	.76		1.000	97	152	97
.2	1.2	.046	.76		1.314	127	160	127
.4	1.4	.054	.76		1.656	164	167	150 ⁺
.6	1.6	.062	.80		2.024	206	173	164 ⁺
.8	1.8	.069	.82		2.445	252	180	173 ⁺
896.0	2.0	.077	.83		2.828	299	186	SAY ORANGE FLOW
.5	2.5	.096	.87		3.953		202	
897.0	3.0	.115	.88		5.196		217	
.5	3.5							
898.0	4.0							
899.0	5.0							
900.0	6.0							
$Q = C, \sqrt{2g} L H^{3/2}$ UNCORRECTED C, $\sqrt{2g} = 3.43$								
$B/W = \frac{5}{6} = .192$ COR ² = 1.03								
⁺ SUBMERGED FLOW - SEE CURVE								

771
BWL 2-52

BAKER RIVER SITE 6

NH - 651-H

HYDRAULIC DESIGN

STAGE DISCHARGE

SHT 206-112

ELEV. LOWER POND	LOW STAGE WEIR	ORIFICE	HIGH STAGE WEIR	TOTAL DISCHARGE				
894.0								
.2	9	120		9				
.4	24	128		24				
.6	45	137		45				
.8	69	144		69				
895.0	97	152		97				
.2	127	160		127				
.4	150	167		150				
.6	164	173		164				
.8	173	180		173				
896.0		186		186				
.5		202		202				
897.0		217		217				
.5		232		232				
898.0		246		246				
899.0		271		271				
900.0		293	(CREST)	293				
900.5		226	118	344				
900.75		224	217	441				
901.0		225	337	562				
901.25		224	480	704				
901.5		223	658	881				
901.75		221	855	1076				
902.0		219	1076	1295				
902.25		217	1320	1537				
902.50		215	1590	1805				
902.75		214	1865	2079				

ASSUME ORIFICE
FLOW

RM - 52

NU - 621-11

STAGE DISCHARGE

SEP 29 1963

[illegible]

SHT 31 OF 42

HYDROGRAPH COMPUTATION

WATERSHED OR PROJECT Upper Pond STATE Illinois

STRUCTURE SITE OR SUBAREA Upper Pond

DR. AREA 12.00 SQ. MI. T_c 5.0 HR. RUNOFF CONDITION NO. 1

RUNOFF CURVE NO. 70 STORM DISTRIB. CURVE 3 HYDROGRAPH FAMILY NO. 1

STORM DURATION 6 HR. RAINFALL: POINT 7 IN. AREAL 72 IN.

Q 2.82 IN. COMPUTED T_p 3.5 HR. T_o 4.36 HR.

$(T_o + T_p)$: COMPUTED 1.25 USED 5 REVISED T_p 2.97

$q_p = \frac{484 A}{REV. T_p} = \frac{484 \times 12}{2.97} = 1630$ CFS. $Q_{dp} = \frac{4690}{60} = 78.17$ CFS.

$t(COLUMN) = (t/T_p) REV. T_p$ $q(COLUMN) = (q_c/q_p) Q_{dp}$

LINE NO.	t HOURS	q CFS	LINE NO.	t HOURS	q CFS	LINE NO.	t HOURS	q CFS
1	0	0	21	17.23	9	41		
2	0.85	129	22	18.07	5	42		
3	1.72	273	23	18.95	0	43		
4	2.58	2069	24			44		
5	3.44	3015	25	AT = 0.0413		45		
6	4.31	3374	26	29 = 21.074		46		
7	5.17	2149	27			47		
8	6.03	2679	28	Q = 0.8413, 21.074		48		
9	6.89	2006	29	645. 10.00		49		
10	7.75	1607	30	= 2.814		50		
11	8.61	915	31			51		
12	9.47	577	32			52		
13	10.34	298	33			53		
14	11.20	262	34			54		
15	12.06	185	35			55		
16	12.92	115	36			56		
17	13.78	77	37			57		
18	14.64	57	38			58		
19	15.50	22	39			59		
20	16.36	11	40			60		

HYDROGRAPH COMPUTATION

SHT 32 OF 42

WATERSHED OR PROJECT _____ STATE _____

STRUCTURE SITE OR SUBAREA _____

DR. AREA _____ SQ. MI. T_c _____ HR. RUNOFF CONDITION NO. _____

RUNOFF CURVE NO. _____ STORM DISTRIB. CURVE _____ HYDROGRAPH FAMILY NO. _____

STORM DURATION _____ HR. RAINFALL: POINT _____ IN. AREAL _____ IN.

Q _____ IN. COMPUTED T_p _____ HR. T_o _____ HR. $(T_o + T_p)$: COMPUTED _____ : USED _____ REVISED T_p _____ $q_p = \frac{484 A}{REV. T_p} = \frac{484 \times 1}{2.2} = 220$ CFS. $Q_{ap} = 6735$ CFS. $t(\text{COLUMN}) = (t/T_p) REV. T_p$. $q(\text{COLUMN}) = (360/q_p) Q_{ap}$

LINE NO.	t HOURS	q CFS	LINE NO.	t HOURS	q' CFS	LINE NO.	t HOURS	q CFS
1	0	0	21	14.13	70	41		
2	1.51	27	22	14.64	13	42		
3	1.91	592	23	14.14	7	43		
4	1.52	1947	24	14.65	0	44		
5	2.03	3295	25	14.65	0	45		
6	2.53	3659	26	14.65	0	46		
7	3.03	3416	27			47		
8	3.53	2998	28			48		
9	4.03	2594	29			49		
10	4.53	220	30			50		
11	5.03	1951	31			51		
12	5.53	1503	32			52		
13	6.03	1004	33			53		
14	6.53	549	34			54		
15	7.03	217	35			55		
16	7.53	122	36			56		
17	8.03	116	37			57		
18	8.53	75	38			58		
19	9.03	54	39			59		
20	9.53	21	40			60		

HYDROGRAPH COMPUTATION

5015X 9174

WATERSHED OR PROJECT _____ STATE _____

STRUCTURE SITE OR SUBAREA 5.1-#6

DR. AREA 6.96 SQ. MI.

T_c 2.0 HR.

RUNOFF CONDITION NO. II

RUNOFF CURVE NO. 70 STORM DISTRIB. CURVE B HYDROGRAPH FAMILY NO. III

STORM DURATION 6 HR.

RAINFALL:

7×1.25
POINT 8.75 IN.

$8.75 \times .89$
AREAL 7.79 IN.

Q 4.27 IN.

COMPUTED T_p 1.4 HR.

T_o 4.76 HR.

$(T_o + T_p)$:

COMPUTED 3.36 :

USED 3.0 :

REVISED T_p 1.57 :

$q_p = \frac{484 A}{REV. T_p} = \underline{2146}$ CFS.

$Qq_p = \underline{9.22}$ CFS.

$t(\text{COLUMN}) = (t/T_p) REV. T_p$

$q(\text{COLUMN}) = (q_c/q_p) Qq_p$

LINE NO.	t HOURS	q CFS	LINE NO.	t HOURS	q CFS	LINE NO.	t HOURS	q CFS
1	2	2	21	10.68	27	41		
2	2.5	37	22	11.21	15	42		
3	3.0	836	23	11.74	0	43		
4	3.5	2648	24	12.27	0	44		
5	4.0	4481	25	12.80	0	45		
6	4.67	4976	26	13.33	26.568	46		
7	5.33	4646	27	13.86		47		
8	6.0	4078	28	14.39	36.568	48		
9	6.67	3528	29	14.92	6.45	49		
10	7.33	3115	30	15.45	6.96	50		
11	8.0	2648	31			51		
12	8.67	2043	32			52		
13	9.33	1365	33			53		
14	10.0	880	34			54		
15	10.67	513	35			55		
16	11.33	307	36			56		
17	12.0	184	37			57		
18	12.67	119	38			58		
19	13.33	73	39			59		
20	14.0	37	40			60		

HYDROGRAPH COMPUTATION

WATERSHED OR PROJECT _____ STATE _____

STRUCTURE SITE OR SUBAREA _____

AREA _____ SQ. MI.

T_c 5.0 HR.

RUNOFF CONDITION NO. _____

RUNOFF CURVE NO. 70 STORM DISTRIB. CURVE B HYDROGRAPH FAMILY NO. _____

FORM DURATION _____ HR.

RAINFALL:

POINT 7.125 8.75 IN.

AREAL 8.75X 861 7.53 IN.

4.06 IN.

COMPUTED T_p 3.5 HR.

T_o 9.69 HR.

$(T_o + T_p)$:

COMPUTED 13.19

USED 15

REVISED T_p 3.13


$Q_p = \frac{484 A}{REV. T_p} = \frac{484 \times 861}{3.13} = 1596$ CFS.

$Q_{ap} = 6217$ CFS.

q (COLUMN) = (t/T_p) REV. T_p .

q (COLUMN) = $(q_c/q_p) Q_{ap}$

LINE NO.	t HOURS	q CFS	LINE NO.	t HOURS	q CFS	LINE NO.	t HOURS	q CFS
	0	0	21	18.15	13	41		
	0.5	76	22	19.06	6	42		
3	1.82	1193	33	19.97	0	43		
	2.72	2325	24	20.88	0	44		
	3.62	4115	25	21.79	0	45		
	4.52	4607	26	22.70	0	46		
	5.42	4300	27	23.61	0	47		
8	6.32	3672	28	24.52	0	48		
	7.26	2793	29	25.43	0	49		
10	8.17	2197	30	26.34	0	50		
	9.08	1249	31	27.25	0	51		
12	9.98	829	32	28.16	0	52		
	10.89	559	33	29.07	0	53		
14	11.80	358	34	30.00	0	54		
	12.71	239	35	30.91	0	55		
16	13.62	157	36	31.82	0	56		
	14.52	94	37	32.73	0	57		
	15.43	50	38	33.64	0	58		
18	16.34	31	39	34.55	0	59		
19	17.25	10	40	35.46	0	60		



AD-A156 415

NATIONAL PROGRAM FOR INSPECTION OF NON-FEDERAL DAMS
BAKER FLOODWATER RESE. (U) CORPS OF ENGINEERS WALTHAM
MA NEW ENGLAND DIV JUL 79


2/2

UNCLASSIFIED


F/G 13/13

NL


END



NATIONAL BUREAU OF STANDARDS
MICROCOPY RESOLUTION TEST CHART



DEPARTMENT OF AGRICULTURE
BUREAU OF PLANT INDUSTRY



APPENDIX E

INFORMATION AS CONTAINED IN
THE NATIONAL INVENTORY OF DAMS

7-74
FEMA

INVENTORY OF DAMS IN THE UNITED STATES

STATE	DIVISION	STATE	COUNTY	CONTRACT	NAME	LATITUDE (NORTH)	LONGITUDE (WEST)	REPORT DATE DAY MO YR
NM	243	NM	009	02	BAKER FLOODWATER RESERVOIR SITE 6	4353.2	7157.5	24 JUL 79

POPULAR NAME	NAME OF IMPOUNDMENT
LOWER BAKER POND DAM	BAKER FLOODWATER RESERVOIR SITE 6
REGION/DASH	NEAREST DOWNSTREAM CITY - TOWN - VILLAGE
01 05	POND BROOK
	POPULATION
	376

TYPE OF DAM	YEAR COMPLETED	PURPOSES	STRAIN HYDRAULIC HEIGHT (FT.)	IMPOUNDING CAPACITIES (ACRES-FT.)	DIST OWN	FED R	PRV/FED	SCS A	VER/DATE
REGG	1971	C	17	13	2240	210	NED	N	N

REMARKS

D/S HAS	SPILLWAY	MAXIMUM DISCHARGE (CFS)	VOLUME OF DAM (CV)	POWER CAPACITY (KW)	INSTALLED	PRODUCED	LENGTH (FT.)	WIDTH (FT.)	HEIGHT (FT.)	WIDTH (FT.)
2	203 U	154	4200	3743						

OWNER	ENGINEERING BY	CONSTRUCTION BY
N M WATER RESOURCES BD	SOIL CONSERVATION SER	ROBIE CONSTRUCTION CO

DESIGN	CONSTRUCTION	OPERATION	MAINTENANCE
NONE	NONE	NONE	NONE

INSPECTION BY	INSPECTION DATE DAY MO YR	AUTHORITY FOR INSPECTION
HOWARD NEEDLES TAMMEN BERGENDOFF	14 MAY 79	PL 92-367

REMARKS

REPRODUCED AT GOVERNMENT EXPENSE

END

FILMED

8-85

DTIC

